

Change Order Number 2

PROJECT:	<u>Eldorado Pkwy (DNT to Preston Rd) / Frisco St (Eldorado Pkwy to Newton Dr)</u>			
PROJECT NUMBER:	<u>CIP 05-0012</u>	BID NUMBER:	<u>0902-0027</u>	
CONTRACT AMOUNT:				
	Original Contract:	<u>\$8,719,172.18</u>	Contract Date	<u>May 1, 2009</u>
	Change Order No. 1	<u>-\$32,331.75</u>	Council Date	<u>September 1, 2009</u>

CONTRACTOR:

Tiseo Paving Company
419 E. Hwy 80
Mesquite, Texas 75150
Phone: (972) 289-0723
Fax: (972) 216-5637

You are directed to make the changes noted below in the subject Contract:

City of Frisco, Texas

By: _____
Name: George Purefoy, City Manager
Dated: _____

Nature of Changes:

1. Remove and replace 12" sanitary sewer. Lower 20" Water Line to avoid sanitary sewer. Existing sewer connection is damaged and must be repaired before a connection can be made. (Items 311A, 404, 501-511)
2. Salvage existing fire hydrants and install deep bury fire hydrants due to depth of the water line. (Items 412, 412A)
3. Correct Drill Shaft elevations at Abutment 6. Drilled shafts were poured to plan elevation before an error in plan elevation was found. (Items 207A)
4. Remove storm drain line F-1 from contract. The storm sewer line will be constructed by TxDOT as part of the Preston Road project. (Items 303, 317, 322, 328,332)
5. Credit for reduced Moisture Conditioning at utility conflicts. (Items 122A)

These changes result in the following adjustment of Contract Price and Contract Time:

I. Paving, Pavement Marking, Traffic & Erosion Control										
Pay Item	Quantity			Units	Description	UNIT COST		TOTAL COST		Change in Cost
	Previous	Change	Revised			Previous	Revised	Previous	Revised	
122A	0.0	-124.0	-124.0	CY	Credit for decreasing depth of moisture conditioning at utility conflicts	\$0.00	\$3.00	\$0.00	(\$372.00)	(\$372.00)
Subtotal										(\$372.00)
II. Bridge										
Pay Item	Quantity			Units	Description	UNIT COST		TOTAL COST		Change in Cost
	Previous	Change	Revised			Previous	Revised	Previous	Revised	
207A	0.0	1.0	1.0	LS	Adjust Abutment #6 Drilled Shaft Elevations	\$0.00	\$3,737.50	\$0.00	\$3,737.50	\$3,737.50
Subtotal										\$3,737.50
III. Storm Drainage										
Pay Item	Quantity			Units	Description	UNIT COST		TOTAL COST		Change in Cost
	Previous	Change	Revised			Previous	Revised	Previous	Revised	
303	1,288.0	-435.0	853.0	LF	18" RCP Class III, including wyes, trench, bedding and backfill, complete	\$34.00	\$34.00	\$43,792.00	\$29,002.00	(\$14,790.00)
311A	0.0	24.0	24.0	LF	Remove & Relay Existing 54" RCP	\$0.00	\$115.00	\$0.00	\$2,760.00	\$2,760.00
317	2.0	-2.0	0.0	EA	8' Recessed Curb Inlet per Detail Sheet D301 of the plans	\$2,320.00	\$2,320.00	\$4,640.00	\$0.00	(\$4,640.00)
322	2.0	-1.0	1.0	EA	TxDOT Type "M" Manhole per Detail Sheet D303 of the plans	\$2,730.00	\$2,730.00	\$5,460.00	\$2,730.00	(\$2,730.00)
328	1.0	-1.0	0.0	EA	36" 6:1 SETP-PD Headwall per Detail Sheet D309	\$2,475.00	\$2,475.00	\$2,475.00	\$0.00	(\$2,475.00)
332	6,502.0	-420.0	6,082.0	LF	Provide Trench Safety Systems for pipelines exceeding 5'-0" in depth in accordance with the Trench Safety Plan and OSHA regulations	\$0.10	\$0.10	\$650.20	\$608.20	(\$42.00)
Subtotal										(\$21,917.00)
IV. Water										
Pay Item	Quantity			Units	Description	UNIT COST		TOTAL COST		Change in Cost
	Previous	Change	Revised			Previous	Revised	Previous	Revised	
404	53.0	15.0	68.0	LF	20" Water Main including trench, bedding, encasement as required	\$185.00	\$185.00	\$9,805.00	\$12,580.00	\$2,775.00
412	5.0	-3.0	2.0	EA	Salvage and Re-install existing Fire Hydrant Assembly per Detail Sheet U301 of the plans, including hydrant extensions, blocking, reflective marker, and all work, complete	\$2,751.00	\$2,751.00	\$13,755.00	\$5,502.00	(\$8,253.00)
412A	0.0	3.0	3.0	EA	Salvage existing Fire Hydrant Assembly and install deep bury Fire Hydrant, including hydrant extensions, blocking, reflective marker, and all work, complete	\$0.00	\$5,595.00	\$0.00	\$16,785.00	\$16,785.00
Subtotal										\$11,307.00

V. Sanitary Sewer										
Pay Item	Quantity			Units	Description	UNIT COST		TOTAL COST		Change in Cost
	Previous	Change	Revised			Previous	Revised	Previous	Revised	
501	228.0	96.0	324.0	LF	12" PVC Sanitary Sewer Pipe, including trench, bedding, backfill	\$46.00	\$46.00	\$10,488.00	\$14,904.00	\$4,416.00
502	40.0	14.0	54.0	LF	12" PVC Pressure Class AWWA C-900 Sanitary Sewer Pipe, including trench, bedding, backfill	\$51.50	\$51.50	\$2,060.00	\$2,781.00	\$721.00
503	1.0	1.0	2.0	EA	Standard 4' Dia. Sanitary Sewer Manhole to 8' depth over existing sanitary sewer	\$2,500.00	\$2,500.00	\$2,500.00	\$5,000.00	\$2,500.00
504	6.0	2.0	8.0	VF	Extra Depth Sanitary Sewer Manhole over 8' depth	\$154.50	\$154.50	\$927.00	\$1,236.00	\$309.00
507	10.0	20.0	30.0	LF	Concrete Encase 12" Sanitary Sewer Main	\$41.20	\$41.20	\$412.00	\$1,236.00	\$824.00
508	268.0	110.0	378.0	LF	Provide Trench Safety Systems for pipelines exceeding 5'-0" in depth in accordance with the Trench Safety Plan and OSHA regulations	\$0.55	\$0.55	\$147.40	\$207.90	\$60.50
510	0.0	1.0	1.0	LS	Sewer Test	\$0.00	\$500.00	\$0.00	\$500.00	\$500.00
511	0.0	110.0	110.0	LF	Remove existing 12" PVC Sanitary Sewer Pipe	\$0.00	\$16.90	\$0.00	\$1,859.00	\$1,859.00
Subtotal										\$11,189.50
Total Cost of Change Order No. 2 =										\$3,945.00


These changes result in the following adjustment of Contract Price and Contract Time:

Contract Price Prior to this Change Order:	\$8,686,840.43
Net change resulting from this Change Order:	\$3,945.00
Contract Price Including this Change Order:	\$8,690,785.43

The Above Changes are Approved:

City of Frisco, Texas

By:




Name: Elizabeth Mettling, P.E.

Title: Assistant Director / City Engineer

Tiseo Paying Company

By:



Name: Robert Caudill

Title: Y.P.